

LOCATION MAP

OWNER INFORMATION:

12881 166TH STREET, CERRITOS, CALIFORNIA 90703 TEL: (714) 227-4887 E-MAÎL: HNGO@GSTES.COM

EARTHWORK QUANTITIES:

CUT:	17 C.Y.	
FILL:	266 C.Y.	
EXPORT:	0 C.Y.	
IMPORT:	0.40	
	0 C.Y.	
OVEREXCAVATION: .		

*EARTHWORK QUANTITIES SHOWN HEREON ARE FOR PERMIT PURPOSES ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING HIS OWN QUANTITIES FOR SOIL ENGINEER: BIDDING PURPOSES. IN ADDITION, EARTHWORK QUANTITIES DO NOT INCLUDE SHRINKAGE, SUBSIDENCE, OVER- EXCAVATION, OR FOOTING EXCAVATIONS.

BENCHMARK:

Underground Service Alert

Call: TOLL FREE

227-2600

1-800

TWO WORKING DAYS BEFORE YOU DIG

THIS TOPOGRAPHIC SURVEY WAS PERFORMED BY SPIRO LAND SURVEYING, INC. ON JANUARY 25TH, 2021. HORIZONTAL CONTROL WAS PER RECORD MONUMENTS ON PARCEL MAP 10489 M.B.P. 98/11 AND BOUNDARY SHOULD NOT BE USED FOR MAPPING PURPOSES. THE BASIS OF BEARING HELD IS N89"11"12"E, THE CENTERLINE OF 166TH ST. THE VERTICAL DATUM WAS ESTABLISHED PER LOS ANGLES COUNTY BENCHMARK 2Y12310, FOUND L&DPW TAG, ELEVATION OF 65.64', PER NAVD 88'

LOT SIZE/GRADING AREA:

LOT AREA (6224-007-002):	2.86 ACRE
AREA OF GRADING:	12,533 SQ. FT.
PROPOSED IMPERVIOUS AREA:	9,665 SQ. FT.
TOTAL IMPERVIOUS AREA:	9,665+94,756=104,4211 SQ. FT

NOTICE TO CONTRACTOR:

CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD DESIGN PROFESSIONAL HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF DESIGN PROFESSIONAL

ENGINEER/SURVEYOR SEAL & SIGNATURE

EARTH STRATA GEOTECHNICAL SERVICES INC 42184 REMINGTON AVENUE, TEMECULA, CALIFORNIA 92590 (951) 397-8315 INFO@EARTH-STRATA.COM

ENGINEER'S/SURVEYOR'S STATEMENT REGARDING THE PRESENCE OF

I HEREBY ATTEST THAT I HAVE LOCATED AND REFERENCED ON THESE

PLANS THE MONUMENTS EXISTING PRIOR TO CONSTRUCTION TO ENSUR

THE BUSINESS AND PROFESSIONS. I FURTHER ATTEST THAT I HAVE

MONUMENTS: SHALL SET SUFFICIENT CONTROLLING, WITNESS, AND

PERPETUATION OF THEIR LOCATION IN ACCORDANCE WITH SECTION 8771

PERMENANT MONUMENTS; AND SHALL FILE THE REQUISITE CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES WITH THE COUNTY SURVEYOR.

EASEMENT NOTES:

1 25' EASEMENT TO THE CITY OF CERRITOS FOR LANDSCAPING PURPOSES PER DOC. 2912, BOOK D-5162, PAGE 82

2 6' EASEMENT TO THE SOUTHERN CALIFORNIA EDISON CO. PER BOOK SCOPE OF WORK: 33169, PAGE 43. O.R.

SHEET INDEX:

G1	_	TITLE SH	EET	
G2	_	NOTES		
G3	_	GRADING	PLAN	1
G4	_	GRADING	PLAN	2

- DETAIL 1

G6 - DETAIL 2

G7 – EROSION CONTROL PLAN

EMERGENCY CONTACT:


IN CASE OF EMERGENCY, PLEASE CONTACT: ALICE WANG (---) --HNGO@GSTES.COM (714) 227-4887

UNAUTHORIZED CHANGES & USES:

CAUTION: THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES TO THE PLANS MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THESE PLANS.

PRECISE GRADING PLAN

GST OFFICE-WAREHOUSE EXPANSION 12881 166TH STREET, CERRITOS, CALIFORNIA 90703 APN: 7010-016-054



GRAPHIC SCALE

PROPOSED 1ST FLOOR WAREHOUSE EXPANSION & 2ND FLOOR COVERED DECK. PROPOSED NEW PLANTER & BOLLARDS FOR EXISTING FIRE HYDRANT. PROPOSED NEW DRIVEWAY & DEMO EXISTING WALL FOR TRUCK LOADING. NEW ADA PATH OF TRAVEL AND NEW PARKING SPACES.

WORK TO BE DONE:

THE WORK PROPOSED BY THIS PROJECT CONSISTS OF THE FOLLOWING WORK TO BE DONE ACCORDING TO THESE PLANS, THE CURRENT LOS ANGELES COUNTY STANDARD DRAWINGS, THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION (MOST CURRENT EDITION) AND ANY APPLICABLE LOS ANGELES COUNTY ORDINANCES.

REFERENCE NOTE:

CONTINUOUS SPECIAL INSPECTION BY THE GEOTECHNICAL ENGINEER IS REQUIRED AND WILL BE PROVIDED IN ACCORDANCE WITH SECTION J107.8

BUILDING CODE:

ALL GRADING AND CONSTRUCTION SHALL CONFORM TO THE 2017 COUNTY OF LOS ANGELES BUILDING CODES

CONSTRUCTION COMPLETION:

START DAY: 10/1/2022 END DAY: 9/30/2023



ITEM	STD./DETAIL	SYMBOL
RIGHT-OF-WAY / PROPERTY LINE		
LIMIT OF WORK		
EXISTING RETAINING WALL		
PROPOSED CONCRETE		4
PROPOSED ASPHALT PAVEMENT		
PROPOSED LANDSCAPE		* * * * * * * * * * * * * * * * * * *
PROPOSED SEWER LINE		ss
PROPOSED WATER LINE		ww
PROPOSED GAS LINE		c c c
PROPOSED CLEANOUT		0
PROPOSED STORM DRAIN LINE		SD SD
PROPOSED CONTOUR		1660
EXISTING CONTOUR		
ADA PATH OF TRAVEL		
PROPOSED CURB		
PROPOSED SWALE		· ·
DEMOLITION AREA		
ADA PATH OF TRAVEL		
SAWCUT AREA		

DECLARATION OF RESPONSIBLE CHARGE ~ CIVIL WORK:

I HEREBY DECLARE THAT I AM THE ENGINEER OF WORK FOR THIS PROJECT, THAT I HAVE EXERCISED RESPONSIBLE CHARGE OVER DESIGN OF THE PROJECT AS DEFINED IN SECTION 6703 OF THE BUSINESS AND PROFESSIONS CODE, AND THAT THE DESIGN IS CONSISTENT WITH CURRENT STANDARDS.

I UNDERSTAND THAT THE CHECK OF PROJECT DRAWINGS AND SPECIFICATIONS BY LOS ANGELES COUNTY IS CONFINED TO REVIEW ONLY AND DOES NOT RELIEVE ME, AS ENGINEER OF WORK, OF MY RESPONSIBILITIES FOR PROJECT DESIGN.

Wilfredo Ventin	10/26/22
WILFREDO S.D. VENTURA, PE C 66532, QSD 21094 EXPIRATION DATE: 6/30/24	DATE
VENTURA ENGINEERING INLAND, INC 27393 YNEZ ROAD, SUITE 159 TEMECULA, CALIFORNIA 92591	
PHONE: (951)252—7632	

WILFREDO@VENTURAENGINEERINGINLAND.COM

DECLARATION OF RESPONSIBLE CHARGE ~ GEOTECHNICAL WORK:

STEPHEN M.POOLE OF EARTH STRATA GEOTECHNICAL SERVICES INC., A REGISTERED CIVIL ENGINEER, PRINCIPALLY DOING BUSINESS IN GEOTECHNICAL ENGINEERING AND/OR APPLIED SOIL MECHANICS, HEREBY CERTIFY THAT A SAMPLING AND STUDY OF THE SOIL CONDITIONS PREVALENT WITHIN THIS SITE WAS MADE BY ME OR UNDER MY DIRECTION. THESE GRADING PLANS HAVE BEEN REVIEWED BY ME OR UNDER MY DIRECTION AND CONFORM TO THE RECOMMENDATIONS MADE IN OUR GEOTECHNICAL ENGINEERING INVESTIGATION REPORT ENTITLED 'PRELIMINARY GEOTECHNICAL INTERPRETIVE REPORT, PROPOSED EXPANSION OF EXISTING COMMERCIAL BUILDING, ASSESSOR'S PARCEL NUMBER 7010-016-054, LOCATED 12881 166TH STREET, CITY OF CERRITOS, LOS ANGELES COUNTY CALIFORNIA DATED NOVEMBER 30,2021.

TO THE BEST OF MY KNOWLEDGE, THE REFERENCED REPORT REPRESENTS THE MOST CURRENT AND COMPLETE INFORMATION RELATIVE TO THE PROPOSED GRADING OF THE SITE.IT IS THE PROFESSIONAL OPINION OF EARTH STRATA GEOTECHNICAL SERVICES INC. THAT THE CONCLUSIONS AND RECOMMENDATIONS RENDERED IN OUR REPORT ARE APPROPRIATE AND APPLICABLE TO THIS PROJECT AND THEY ARE IN SUBSTANTIAL CONFORMANCE WITH ALL APPLICABLE CODE, ORDINANCE, AND STANDARDS OF PRACTICE FOR THE PROJECT





ENGINEER / ARCHITECT STATEMENT REGARDING LID:

AS THE ARCHITECT OR ENGINEER OF THE PROJECT, I HAVE REVIEWED THE LOW IMPACT DEVELOPMENT (LID) STANDARDS MANUAL BY COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS, AND HAVE PROPOSED THE IMPLEMENTATION OF THE PERMANENT BEST MANAGEMENT PRACTICES (BMPS) APPLICABLE TO EFFECTIVELY MINIMIZE THE NEGATIVE IMPACTS OF THE PROJECT'S STORMWATER RUNOFF. THE SELECTED BMPS WILL BE INSTALLED PER THE APPROVED PLANS AND AS RECOMMENDED BY THE PRODUCT MANUFACTURER

AS THE ARCHITECT/ENGINEER OF RECORD, I HAVE SELECTED APPROPRIATE BMPS TO EFFECTIVELY MINIMIZE THE NEGATIVE IMPACTS OF THIS PROJECT'S CONSTRUCTION ACTIVITIES ON STORM WATER QUALITY. THE PROJECT OWNER AND CONTRACTOR ARE AWARE THAT THE SELECTED BMPS MUST BE INSTALLED, MONITORED, AND MAINTAINED TO ENSURE THEIR EFFECTIVENESS. THE BMPS NOT SELECTED FOR IMPLEMENTATION ARE REDUNDANT OR DEEMED NOT APPLICABLE TO THE PROPOSED CONSTRUCTION ACTIVITY."

NAME OF SIGNER SIGNITURE OF SIGNER

> 27393 YNEZ ROAD, SUITE 159 WILFREDO S.D. VENTURA No. 66532 Exp. 6-30-24 CIVIL RCE 66532, EXP. 6/30/24

TITLE SHEET

G1

		CITY OF CER
VENTURA ENGINEERING INLAND	INIC	

TEMECULA, CALIFORNIA 92591 PHONE: (951)252-7632 WILFREDO@VENTURAENGINEERINGINLAND.COM

Wilfredo Vinter WILFREDO S.D. VENTURA DATE

Ventura Engineering Inland INC

A.P.N. 7010-016-054

CIVIL SHEET 1 OF 7

APPROVED BY DATE **REVISIONS** REVISED BY

SCALE: 1" = 40'

REGULAR GRADING REQUIREMENTS [J105.7]:

- 27. THE PERMITTEE OR HIS AGENT SHALL NOTIFY THE BUILDING OFFICIAL 24 HOURS BEFORE THE GRADING OPERATION IS READY FOR EACH OF THE INSPECTIONS:

 A. PRE-GRADE INSPECTION: WHEN THE PERMITTEE IS READY TO BEGIN WORK AND BEFORE
- ANY GRADING OR BRUSHING IS STARTED.

 B. INITIAL GRADE: WHEN THE SITE HAS BEEN CLEARED OF VEGETATION AND UNAPPROVED FILL AND HAS BEEN SCARIFIED, BENCHED, OR OTHERWISE PREPARED FOR FILL. NO FILL SHALL HAVE BEEN PLACED PRIOR TO THIS INSPECTION.
- C. <u>ROUGH GRADING</u>: WHEN APPROXIMATE FINAL ELEVATIONS HAVE BEEN ESTABLISHED, DRAINAGE TERRACES, SWALES, AND OTHER DRAINAGE DEVICES NECESSARY FOR THE PROTECTION OF THE BUILDING SITES FROM FLOODING HAVE BEEN INSTALLED, BERMS HAVE BEEN INSTALLED AT THE TOP OF SLOPES, AND THE STATEMENTS REQUIRED BY SECTION J105.12 HAVE BEEN RECEIVED.
- D. <u>FINAL INSPECTION:</u> WHEN ALL WORK, INCLUDING INSTALLATION OF ALL DRAINAGE STRUCTURES AND OTHER PROTECTIVE DEVICES, HAS BEEN COMPLETED AND THE AS-GRADED PLAN AND REQUIRED REPORTS HAVE BEEN SUBMITTED.

ENGINEERED GRADING REQUIREMENT [J107.5]:

- 28. FILL SHALL BE COMPACTED TO NOT LESS THAN 90% OF MAXIMUM DENSITY WITHIN 40 FEET OF THE FINISHED GRADE AND 93% OF MAXIMUM DENSITY DEEPER THAN 40 FEET BELOW FINISHED GRADE AS DETERMINED BY A.S.T.M. SOIL COMPACTION TEST D1557, MODIFIED
- 29. FIELD DENSITY SHALL BE DETERMINED BY SAND—CONE METHOD, A.S.T.M. D1556—LATEST VERSION. IN FINE—GRAINED COHESIVE SOILS FIELD DENSITY MAY BE DETERMINED BY THE DRIVE—CYLINDER METHOD, A.S.T.M. D—2937— LATEST VERSION, PROVIDED NOT LESS THAN 10% OF THE REQUIRED DENSITY TESTS, UNIFORMLY DISTRIBUTED, ARE BY THE SAND—DONE METHOD. THE METHOD OF DETERMINING FIELD DENSITY SHALL BE SHOWN IN THE COMPACTION REPORT. OTHER METHODS MAY BE USED IF RECOMMENDED BY THE SOILS ENGINEER AND APPROVED IN ADVANCE BY THE BUILDING OFFICIAL.
- 30. SUFFICIENT TESTS OF SOIL PROPERTIES, INCLUDING SOIL TYPES AND SHEAR STRENGTH, SHALL BE MADE DURING GRADING OPERATIONS TO VERIFY COMPLIANCE WITH DESIGN CRITERIA. THE RESULTS OF SUCH TESTING SHALL BE FURNISHED TO THE BUILDING OFFICIAL UPON COMPLETION OF GRADING OPERATIONS, OR WHEN NECESSITATED BY FIELD CONDITIONS UPON REQUEST OF THE BUILDING OFFICIAL. ONE FIELD DENSITY TEST TO BE MADE AS FOLLOWS:
- A. ONE TEST FOR EACH TWO FOOT VERTICAL LEFT.

 B. ONE TEST FOR EACH 1,000 CUBIC YARD OF MATERIAL PLACED.

 C. ONE TEST WILL BE MADE AT POINT APPROXIMATELY ONE FOOT BELOW THE FILL S
- C. ONE TEST WILL BE MADE AT POINT APPROXIMATELY ONE FOOT BELOW THE FILL SLOPE SURFACE ON THE BASIS OF ONE TEST FOR EACH 1,000 SQUARE FEET OF SLOPE SURFACE BUT NOT LESS THAN ONE TEST FOR EACH 10 FOOT OF VERTICAL SLOPE HEIGHT.
- 31. NO FILL SHALL BE PLACED UNTIL STRIPPING OF VEGETATION, REMOVAL OF UNSUITABLE SOILS, AND INSTALLATION OF SUBDRAINS (IF ANY) HAVE BEEN INSPECTED AND APPROVED BY THE SOILS ENGINEER
- 32. NO ROCK OR SIMILAR MATERIAL GREATER THAN 12 INCHES IN DIAMETER WILL BE PLACED IN THE FILL UNLESS RECOMMENDATIONS FOR SUCH PLACEMENT HAVE BEEN SUBMITTED BY THE SOILS ENGINEER AND APPROVED IN ADVANCE BY THE BUILDING OFFICIAL.
- 33. CONTINUOUS INSPECTION BY THE SOILS ENGINEER OR HIS RESPONSIBLE REPRESENTATIVE SHALL BE PROVIDED DURING ALL FILL PLACEMENT AND COMPACTION OPERATIONS WHERE FILLS HAVE A DEPTH GREATER THAN 30 FEET OR A SLOPE SURFACE STEEPER THAN 2:1. [J107.8]
- 34. CONTINUOUS INSPECTION BY THE SOILS ENGINEER OR HIS RESPONSIBLE REPRESENTATIVE SHALL BE PROVIDED DURING ALL SUBDRAIN INSTALLATIONS. [J107.2]

GENERAL NOTES:

- 68. ANY MODIFICATIONS OF OR CHANGES IN APPROVED GRADING PLANS MUST BE APPROVED BY
- THE BUILDING OFFICIAL.
 69. A COPY OF THE GRADING PERMIT AND APPROVED GRADING PLAN MUST BE IN THE POSSESSION OF A RESPONSIBLE PERSON AND AVAILABLE AT THE SITE. [J103.4]
- 70. ENGINEER MUST SET GRADE STAKES FOR ALL DRAINAGE DEVICES AND OBTAIN INSPECTION
- 71. ALL STORM DRAIN WORK IS TO BE DONE UNDER CONTINUOUS INSPECTION BY THE FIELD ENGINEER. WEEKLY STATUS REPORTS SHALL BE SUBMITTED BY THE FIELD ENGINEER TO THE CITY BUILDING DEPARTMENT. [J105.2]
- 72. PROVISIONS SHALL BE MADE FOR CONTRIBUTORY DRAINAGE AT ALL TIMES.
- 73. SECURE PERMISSION FROM (CITY ENGINEER), (STATE HIGHWAY DEPARTMENT) OR THE MAINTENANCE ASSOCIATION RESPONSIBLE FOR THE PRIVATE STREET, FOR CONSTRUCTION, GRADING AND/OR DISCHARGE OF DRAINAGE WITHIN STREET RIGHT—OF—WAY.
- 74. THE GRADING CONTRACTOR SHALL SUBMIT A WRITTEN STATEMENT VERIFYING THAT THE WORK DONE UNDER HIS DIRECTION WAS PERFORMED IN ACCORDANCE WITH THE APPROVED PLANS AND REQUIREMENTS OF THE CITY BUILDING CODE OR DESCRIBING ALL VARIANCES FROM THE APPROVED PLANS AND REQUIREMENTS OF THE CODE. [J105.12.4]
- 75. THE DESIGN ENGINEER VERIFIES THAT THIS GRADING PLAN WAS PREPARED UNDER MY SUPERVISION IN ACCORDANCE WITH THE CITY BUILDING CODE. ALL SOILS ENGINEER AND ENGINEERING GEOLOGY RECOMMENDATIONS WERE INCORPORATED IN PLAN. (MUST BE SIGNED AND DATED BY THE DESIGN ENGINEER.)
- 76. DESIGN AND TESTING OF PRESTRESSED ROCK OR STONE TIE BACK ANCHORS SHALL MEET THE STANDARDS SET OUT IN SECTION J106.2.4. THE SPECIFICATIONS CONTAINED THERE IN SHALL BE ADDED TO THE PLANS.
- 77. ALL RECOMMENDATIONS INCLUDED IN THE CONSULTANT'S SOIL AND GEOLOGY REPORTS MUST BE COMPLIED WITH AND ARE A PART OF THE GRADING SPECIFICATIONS.
- 78. GRADING OPERATIONS MUST BE CONDUCTED UNDER PERIODIC GEOLOGIC INSPECTION WITH MONTHLY INSPECTION REPORTS TO BE SUBMITTED TO THE CITY BUILDING DEPARTMENT.
- 79. THE CONSULTING GEOLOGIST MUST APPROVE ROUGH GRADING BY FINAL REPORT. FINAL REPORT MUST INCLUDE AN AS-BUILT GEOLOGIC MAP.
- 80. GRADING SHALL NOT BE STARTED WITHOUT FIRST NOTIFYING THE GRADING INSPECTOR. A PRE—GRADING MEETING ON THE SITE IS REQUIRED BEFORE START OF GRADING WITH THE FOLLOWING PEOPLE PRESENT: OWNER, GRADING CONTRACTOR, DESIGN CIVIL ENGINEER, SOIL ENGINEER, GEOLOGIST, GRADING INSPECTOR, AND WHEN REQUIRED, THE ARCHAEOLOGIST AND PALEONTOLOGIST. THE REQUIRED INSPECTIONS FOR GRADING WILL BE EXPLAINED AT THIS
- MEETING. [J105.7] 81. AREAS TO RECEIVE FILL SHALL BE PROPERLY PREPARED AND APPROVED, IN WRITING, BY THE SOIL ENGINEER AND THE BUILDING OFFICIAL PRIOR TO PLACING FILL.
- 82. FILL SHALL BE BENCHED INTO COMPETENT MATERIAL PER SOILS ENGINEERS DIRECTIONS.
- 83. ALL EXISTING FILLS SHALL BE APPROVED BY THE BUILDING OFFICIAL OR REMOVED PRIOR TO PLACING ADDITIONAL FILLS.
- 84. STOCK PILING OF EXCESS MATERIAL SHALL BE APPROVED BY THE BUILDING OFFICIAL PRIOR TO EXCAVATION.
- 85. THE FIELD ENGINEER, AS A CONDITION OF ROUGH GRADE APPROVAL, SHALL PROVIDE A BLUE TOP WITH ACCOMPANYING WITNESS STAKE, SET AT THE CENTER OF EACH PAD REFLECTING THE PAD ELEVATION FOR PRECISE PERMITS AND A BLUE TOP WITH WITNESS STAKE SET AT THE DRAINAGE SWALE HIGH POINT REFLECTING THE HIGH POINT ELEVATION FOR PRELIMINARY PERMITS. [J105.3]
- 86. ALL TRENCH BACKFILLS SHALL BE TESTED AND APPROVED BY THE SOIL ENGINEER.
 87. THE ENGINEERING GEOLOGIST AND SOIL ENGINEER SHALL, AFTER CLEARING AND PRIOR TO THE PLACEMENT OF FILL IN CANYONS, INSPECT EACH CANYON FOR AREAS OF ADVERSE STABILITY AND TO DETERMINE THE PRESENCE OF ABSENCE OF SUBSURFACE WATER OR SPRING FLOW. IF NEEDED, SUB-DRAINS WILL BE DESIGNED AND CONSTRUCTED PRIOR TO
- THE PLACEMENT OF FILL IN EACH RESPECTIVE CANYON.

 88. SUB-DRAIN OUTLETS SHALL BE COMPLETED AT THE BEGINNING OF THE SUB-DRAIN CONSTRUCTION AND SURVEY FOR LOCATION. THE AS GRADED PLAN SHALL SHOW ALL SUB-DRAIN LOCATIONS AND ELEVATIONS.
- 89. ALL CUT SLOPES SHALL BE INVESTIGATED BOTH DURING AND AFTER GRADING BY THE ENGINEERING GEOLOGIST TO DETERMINE IF ANY SLOPE STABILITY PROBLEM EXISTS. SHOULD EXCAVATION DISCLOSE ANY GEOLOGICAL HAZARDS OR POTENTIAL GEOLOGICAL HAZARDS, THE ENGINEERING GEOLOGIST SHALL SUBMIT RECOMMENDED REMEDIATION TO THE BUILDING OFFICIAL FOR APPROVAL.
- 90. WHERE SUPPORT OR BUTTRESSING OF CUT AND NATURAL SLOPES IS DETERMINED TO BE NECESSARY BY THE ENGINEERING GEOLOGIST AND SOIL ENGINEER, THE SOIL ENGINEER SHALL SUBMIT DESIGN, LOCATIONS, AND CALCULATIONS TO THE BUILDING OFFICIAL PRIOR TO CONSTRUCTION. THE ENGINEERING GEOLOGIST AND SOIL ENGINEER SHALL INSPECT AND CONTROL THE CONSTRUCTION OF THE BUTTRESSING AND CERTIFY TO THE STABILITY OF THE SLOPE AND ADJACENT STRUCTURES UPON COMPLETION.
- 91. WHEN CUT PADS ARE BROUGHT TO NEAR GRADE, THE ENGINEERING GEOLOGIST SHALL DETERMINE IF THE BEDROCK IS EXTENSIVELY FRACTURED OR FAULTED AND WILL READILY TRANSMIT WATER. IF CONSIDERED NECESSARY BY THE ENGINEERING GEOLOGIST AND SOIL ENGINEER, A COMPACTED FILL BLANKET WILL BE PLACED. [J105.5]
- 92. THE COMPACTION REPORT AND APPROVAL FROM THE SOIL ENGINEER SHALL INDICATE THE TYPE OF FIELD TESTING PERFORMED. EACH TEST SHALL BE IDENTIFIED WITH THE METHOD OF OBTAINING THE IN-PLACE DENSITY, WHETHER SAND CONE OR NUCLEAR GAUGE, AND SHALL BE SO NOTED FOR EACH TEST. [J105.4]
- 93. EXPORT SOIL MUST BE TRANSPORTED TO A LEGAL DUMP OR TO A PERMITTED SITE SHOWN CLEARLY ON APPROVED PLANS.
- 94. THE ENGINEER SHALL SUBMIT A LETTER OF CERTIFICATION TO THE BUILDING OFFICIAL STATING THAT THE GRADING WAS DONE IN COMPLIANCE WITH THE APPROVED GRADING PLAN. 95. PRELIMINARY SOIL AND GEOLOGY REPORTS AND ALL SUBSEQUENT REPORTS ARE CONSIDERED
- A PART OF THE APPROVED GRADING PLAN. ALL RECOMMENDATIONS CONTAINED ARE TO BE COMPLIED WITH OR REVISIONS SUBMITTED FOR REVIEW.

 96. ALL EXISTING DRAINAGE COURSES THROUGH THIS SITE SHALL REMAIN OPEN UNTIL FACILITIES


TO HANDLE STORM WATER ARE APPROVED AND FUNCTIONAL; HOWEVER, IN ANY CASE, THE


PERMITTEE SHALL BE HELD LIABLE FOR ANY DAMAGE DUE TO OBSTRUCTING NATURAL DRAINAGE PATTERNS.


97. ANY EXCAVATIONS ADJACENT TO OTHER PROPERTY OR STRUCTURES ARE SUBJECT TO THE PROVISIONS OF CALIFORNIA CIVIL CODE, SECTION 832, AND IS THE RESPONSIBILITY OF THE


PERMITTEE AND/OR OWNER.


NOTES CITY OF CERRITOS **REVISIONS** REVISED BY APPROVED BY DATE VENTURA ENGINEERING INLAND, INC 27393 YNEZ ROAD, SUITE 159 TEMECULA, CALIFORNIA 92591 WILFREDO S.D. VENTURA PHONE: (951)252-7632 WILFREDO@VENTURAENGINEERINGINLAND.COM No. <u>66532</u> Exp. 6-30-24 Wilfredo Vinter CIVIL Ventura Engineering Inland INC WILFREDO S.D. VENTURA DATE RCE 66532, EXP. 6/30/24 A.P.N. 7010-016-054 CIVIL SHEET 2 OF 7



















2 RIBBON GUTTER DETAIL:

NOT TO SCALE


PROVIDE EXPANSION JOINTS AT 60' O.C. MAX W/WEAKENED PLANE JOINTS AT 20' O.C. INSTALL 3"X36" LONG DOWELS AT 12" O,C, AT EXPANSION JOINTS.

						DETAILS		G5
NO.	REVISIONS	REVISED BY	APPROVED BY	DATE		CITY OF CER	RITOS	
					PROFESSIONAL PROFE	VENTURA ENGINEERING INLAND, INC 27393 YNEZ ROAD, SUITE 159 TEMECULA, CALIFORNIA 92591 PHONE: (951)252–7632 WILFREDO@VENTURAENGINEERINGINLAND.COM Wilfredo Vintura 10/26/22 WILFREDO S.D. VENTURA RCE 66532, EXP. 6/30/24	Ventura Engineeri	ng Inland INC
					PROJECT ENGINEER DATE	A.P.N. 7010-016-054	CIVIL SHEET 5 C	OF 7

ACCEPTABLE FILL MATERIALS: STORMTECH MC-7200 CHAMBER SYSTEMS


MATERIAL LOCATION		DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 24" (600 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 12" (300 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS.
В	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	NO COMPACTION REQUIRED.
А	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ^{2,3}

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE". STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9" (230 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS
- 4. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



- 1. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" CHAMBER CLASSIFICATION 60x101
- 2. MC-7200 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". 3. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION
- FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 4. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS. 5. REQUIREMENTS FOR HANDLING AND INSTALLATION:
- TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
- TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 3".
- TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 500 LBS/FT/%. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

MC-7200 CROSS SECTION DETAIL




INSPECTION & MAINTENANCE

- STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT A. INSPECTION PORTS (IF PRESENT)
 - A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
 - A.3. USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON
 - MAINTENANCE LOG A.4. LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS
 - A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3. B. ALL ISOLATOR PLUS ROWS
 - REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS B.2. USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE i) MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY ii) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
- B.3. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3. STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
 - A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS
 - B. APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN C. VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.


- 1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
- 2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS

MC-7200 ISOLATOR ROW PLUS DETAIL


STORMTECH SYSTEM DETAIL NOT TO SCALE










INSERTA-TEE SIDE INLET DETAIL









						STORMTECH SYST	EM DETAIL G6
NO.	REVISIONS	REVISED BY	APPROVED BY	DATE		CITY OF CER	RITOS
					PROFESSIONA WILFREDO S.D. VENTURA No. 66532 Exp. 6-30-24 CIVIL OF CALFORN CF CALFORN CONTRACT CF CALFORN CONTRACT CO	VENTURA ENGINEERING INLAND, INC 27393 YNEZ ROAD, SUITE 159 TEMECULA, CALIFORNIA 92591 PHONE: (951)252–7632 WILFREDO@VENTURAENGINEERINGINLAND.COM Wilfredo Vitter 10/26/22 WILFREDO S.D. VENTURA DATE RCE 66532, EXP. 6/30/24	Ventura Engineering Inland INC
					PROJECT ENGINEER DATE	A.P.N. 7010-016-054	CIVIL SHEET 6 OF 7

PARCEL 4 PARCEL 3 **EROSION CONTROL STREET SWEEPING NOTE: SCHEMATIC NOTE: CONSTRUCTION NOTES SYMBOL** 294.72' CONTRACTOR TO SWEEP THE STREET AFTER EVERY TRUCK THIS EROSION CONTROL PLAN IS SCHEMATIC IN NATURE N89°11'57"E 375.40' DELIVERY AND AT THE END OF EACH WORK DAY FOLLOWING ALL ONLY AND CAN BE MODIFIED AS NEEDED BY THE ─ INSTALL DOUBLE ROW OF GRAVEL BAGS & INLET PROTECTION 892 L.F STANDARD PRACTICES FOR WATERLESS STREET SWEEPING. CONTRACTOR DURING CONSTRUCTION AND WILL CONSENT / (SE-6 & SE-10 PER CASQA). OF THE CITY INSPECTOR. $\langle \overline{2} \rangle$ INSTALL CONCRETE WASHOUT CONTAINER (WM-8 PER CASQA). 1 EA. **EROSION AND SEDIMENT CONTROL PLAN GENERAL NOTES:** ESTABLISH EQUIPMENT & MATERIAL STORAGE AREA PER CALTRANS (3) WASTE MANAGEMENT AND MATERIALS POLLUTION CONTROL BEST 1 EA. IN CASE OF EMERGENCY, CALL (RESPONSIBLE PERSON) AT (24-HOUR TELEPHONE). MANAGEMENT PRACTICES (WM-1 PER CASQA). PLEASE FILL IN NAME AND NUMBER TOTAL DISTURBED AREA 12,458 SF WDID # ----RISK LEVEL 1 2 3 (CIRCLE ONE AS DETERMINED BY STATE GENERAL PERMIT FOR SITES GREATER THAN 1 ACRE) ESTABLISH STOCKPILE MANAGEMENT AREA PER CALTRANS WASTE 1 EA. A STAND-BY CREW FOR EMERGENCY WORK SHALL BE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON (NOVEMBER 1 TO APRIL 15). MANAGEMENT AND MATERIALS POLLUTION CONTROL BEST MANAGEMENT NECESSARY MATERIALS SHALL BE AVAILABLE ON-SITE AND STOCKPILED AT CONVENIENT LOCATIONS TO FACILITATE RAPID CONSTRUCTION OF EMERGENCY DEVICES WHEN RAIN IS IMMINENT. PRACTICES (WM-5 PER CASQA). EROSION CONTROL DEVICES SHOWN ON THIS PLAN MAY BE REMOVED WHEN APPROVED BY THE BUILDING OFFICIAL IF THE GRADING OPERATION HAS PROGRESSED TO THE POINT WHERE THEY ARE NO LONGER REQUIRED. (5) INSTALL STABILIZED CONSTRUCTION ENTRANCE (TC-1 PER CASQA). 1 EA. GRADED AREAS ADJACENT TO FILL SLOPES LOCATED AT THE SITE PERIMETER MUST DRAIN AWAY FROM THE TOP OF SLOPE AT THE CONCLUSION OF EACH WORKING DAY. ALL LOOSE SOILS AND DEBRIS THAT MAY CREATE A POTENTIAL HAZARD TO OFF-SITE PROPERTY SHALL BE STABILIZED OR REMOVED FROM THE SITE ON A DAILY BASIS. ⟨ 6 ⟩ INSTALL PORTABLE TOILET (WM-9 PER CASQA). ALL SILT AND DEBRIS SHALL BE REMOVED FROM ALL DEVICES WITHIN 24 HOURS AFTER EACH RAINSTORM AND BE DISPOSED OF PROPERLY. 1 EA. A GUARD SHALL BE POSTED ON THE SITE WHENEVER THE DEPTH OF WATER IN ANY DEVICE EXCEEDS TWO FEET. THE DEVICE SHALL BE DRAINED OR PUMPED DRY WITHIN 24 HOURS AFTER EACH RAINSTORM. PUMPING AND DRAINING OF ALL BASINS AND DRAINAGE DEVICES MUST COMPLY MUST COMPLY WITH THE APPROPRIATE BMP FOR DEWATERING OPERATIONS. THE PLACEMENT OF ADDITIONAL DEVICES TO REDUCE EROSION DAMAGE AND CONTAIN POLLUTANTS WITHIN THE SITE IS LEFT TO THE DISCRETION OF THE FIELD ENGINEER. ADDITIONAL DEVICES AS NEEDED SHALL BE INSTALLED TO RETAIN SEDIMENTS AND OTHER POLLUTANTS DESILTING BASINS MAY NOT BE REMOVED OR MADE INOPERABLE BETWEEN NOVEMBER 1 AND APRIL 15 OF THE FOLLOWING YEAR WITHOUT THE APPROVAL OF THE BUILDING OFFICIAL. **QSD CERTIFICATION:** O. STORM WATER POLLUTION AND EROSION CONTROL DEVICES ARE TO BE MODIFIED, AS NEEDED, AS THE PROJECT PROGRESSES, THE DESIGN AND PLACEMENT OF THESE DEVICES IS THE RESPONSIBILITY OF THE FIELD ENGINEER. PLANS REPRESENTING CHANGES MUST BE SUBMITTED FOR APPROVAL IF REQUESTED BY THE BUILDING OFFICIAL. I HEREBY DECLARE THAT I AM THE ENGINEER OF WORK FOR THIS PROJECT, EVERY EFFORT SHOULD BE MADE TO ELIMINATE THE DISCHARGE OF NON-STORM WATER FROM THE PROJECT SITES AT ALL TIMES. THAT I HAVE EXERCISED RESPONSIBLE CHARGE OVER THE DESIGN OF THE 2. ERODED SEDIMENTS AND OTHER POLLUTANTS MUST BE RETAINED ON-SITE AND MAY NOT BE TRANSPORTED FROM THE SITE VIA SHEET FLOW, PROJECT AS DEFINED IN SECTION 6703 OF THE BUSINESS AND PROFESSIONS SWALES, AREA DRAINS, NATURAL DRAINAGE COURSES, OR WIND. CODE, AND THAT THE DESIGN IS CONSISTENT WITH CURRENT STANDARDS. STOCKPILES OF EARTH AND OTHER CONSTRUCTION-RELATED MATERIALS MUST BE PROTECTED FROM BEING TRANSPORTED FROM THE SITE BY THE FORCES OF WIND OR WATER. 4. FUELS. OILS. SOLVENTS, AND OTHER TOXIC MATERIALS MUST BE STORED IN ACCORDANCE WITH THEIR LISTING AND ARE NOT TO CONTAMINATE I HAVE COMPLIED WITH THE CRITERIA OF MWELO AND APPLIED THE THE SOILS AND SURFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER. SPILLS MUST BE REQUIREMENTS ACCORDINGLY FOR THE EFFICIENT USE OF WATER IN THE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MAY NOT BE WASHED INTO THE DRAINAGE SYSTEM. GRADING DESIGN PLAN. 5. EXCESS OR WASTE CONCRETE MAY NOT BE WASHED INTO THE PUBLIC WAY OR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON-SITE UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE . DEVELOPERS/CONTRACTORS ARE RESPONSIBLE TO INSPECT ALL EROSION CONTROL DEVICES AND BMPS ARE INSTALLED AND FUNCTIONING PROPERLY IF THERE IS A 50% OR GREATER PROBABILITY OF PREDICTED PRECIPITATION, AND AFTER ACTUAL PRECIPITATION. A CONSTRUCTION SITE INSPECTION CHECKLIST AND INSPECTION LOG SHALL BE MAINTAINED AT THE PROJECT SITE AT ALL TIMES AND AVAILABLE FOR REVIEW BY WILFREDO S.D. VENTURA, PE C 66532, QSD 21094 DATE PARCEL 6 THE BUILDING OFFICIAL (COPIES OF THE SELF-INSPECTION CHECK LIST AND INSPECTION LOGS ARE AVAILABLE UPON REQUEST). EXPIRATION DATE: 06/30/24 TRASH AND CONSTRUCTION-RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION OF SEDIMENTS AND OTHER MATERIALS MAY NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONSTRUCTION ENTRANCE ROADWAYS VENTURA ENGINEERING INLAND, INC MUST BE STABILIZED SO AS TO INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC WAY. ACCIDENTAL DEPOSITIONS MUST BE SWEPT FF 66.00 27393 YNEZ RD. SUITE 159 FF 66.00 UP IMMEDIATELY AND MAY NOT BE WASHED DOWN BY RAIN OR OTHER MEANS. PAD 65.25 TEMECULA, CALIFORNIA 92562 PAD 65.25 19. ANY SLOPES WITH DISTURBED SOILS OR DENUDED OF VEGETATION MUST BE STABILIZED SO AS TO INHIBIT EROSION BY WIND AND WATER. 4,325 SF TOLL FREE (800) 723-4224 4,825 SF 20. AS THE ENGINEER/OSD OF RECORD, I HAVE SELECTED APPROPRIATE BMPS TO EFFECTIVELY MINIMIZE THE NEGATIVE IMPACTS OF THIS PROJECT'S CONSTRUCTION ACTIVITIES ON STORM WATER QUALITY. THE PROJECT OWNER AND CONTRACTOR ARE AWARE THAT THE SELECTED **RE-VEGETATION NOTE:** BMPS MUST BE INSTALLED. MONITORED. AND MAINTAINED TO ENSURE THEIR EFFECTIVENESS. **EXISTING** FF 66.00 ONCE CONSTRUCTION IS COMPLETE, RE-VEGETATE AREAS PAD 65.25 OUTSIDE THE GRADING ENVELOPE THAT WERE DISTURBED AS PART OF THE CONSTRUCTION PROCESS. CIVIL ENGINEER/QSD SIGNATURE DATE THE FOLLOWING NOTES MUST BE ON THE PLAN: AS THE PROJECT OWNER OR AUTHORIZED AGENT OF THE OWNER, 1 CERTIFY THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH THE SYSTEM DESIGNED T CONSTRUCTION ENTRANCE NOTE: PERSON OR PERSONS WHO MANAGE THE SYSTEM OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION. TO THE BEST OF MY KNOWLEDGE AND BELIEF, THE INFORMATION SUBMITTED IS TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT SUBMITTING A STABILIZED CONSTRUCTION ENTRANCE IS TO BE USED AS LONG AS FEASIBLE. IT IS FALSE AND/ OR INACCURATE INFORMATION, FAILING TO UPDATE THE ESCP TO REFLECT CURRENT CONDITIONS, OR FAILING TO PROPERLY ANTICIPATED THAT THE ENTRANCE WILL BE REMOVED ONCE SITE EARTHWORK AND/OR ADEQUATELY IMPLEMENT THE ESCP MAY RESULT IN REVOCATION OF GRADING AND/OR OTHER PERMITS OR OTHER SANCTIONS = $_{4}$ = $_{50}$ - - $_{50}$ + +OPERATIONS, RETAINING WALLS ARE INSTALLED, AND SLABS HAVE BEEN POURED. PROVIDED BY LAW." **EXISTING UTILITY NOTE:** OWNER OR AUTHORIZED REPRESENTATIVE (PERMITTEE) DATE 22. DEVELOPERS/CONTRACTORS ARE RESPONSIBLE TO INSPECT ALL EROSION CONTROL DEVICES AND BMPS ARE INSTALLED AND FUNCTIONING CONTRACTOR TO PROTECT ALL EXISTING UTILITIES DURING PROPERLY AS REQUIRED BY THE STATE CONSTRUCTION GENERAL PERMIT. A CONSTRUCTION SITE INSPECTION CHECKLIST AND INSPECTION LC CONSTRUCTION ACTIVITIES. SHALL BE MAINTAINED AT THE PROJECT SITE AT ALL TIMES AND AVAILABLE FOR REVIEW BY THE BUILDING OFFICIAL. 3. THE FOLLOWING BMPS FROM THE "2009 CONSTRUCTION BMP HANDBOOK/PORTAL" MUST BE IMPLEMENTED FOR ALL CONSTRUCTION ACTIVITIES AS APPLICABLE. AS AN ALTERNATIVE, DETAILS FROM "CALTRANS STORMWATER QUALITY HANDBOOKS, CONSTRUCTION SITE BEST MANAGEMENT PRACTICES (BMP) MANUAL"MAY BE USED. ADDITIONAL MEASURES MAY BE REQUIRED IF DEEMED APPROPRIATE BY THE BUILDING OFFICIAL. **UNAUTHORIZED CHANGES & USES:** OWNERS CERTIFICATE NOTE: CAUTION: THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE 1 CERTIFY THAT THIS WATER QUALITY DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ACCORDANCE WITH A SYSTEM DESIGNED TO ENSURE THAT QUALIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE WATER QUALITY ALL CHANGES TO THE PLANS MUST BE IN WRITING AND MUST BE APPROVED BY INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE PREPARATION OF PLANS OR THOSE THE PREPARER OF THESE PLANS. PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, TO THE BEST OF MY KNOWLEDGE AND BELIEF, THE INFORMATION 30' MIN. SUBMITTED IS TRUE, ACCURATE, AND COMPLETE AS IT RELATES TO WATER QUALITY. I AM AWARE THAT SUBMITTING FALSE AND/OR INACCURATE INFORMATION, FAILING TO UPDATE THE ESCP TO REFLECT CURRENT CONDITIONS, OR FAILING TO PROPERLY AND / OR **ADEQUATELY** IMPLEMENT THE ESCP MAY RESULT IN REVOCATION OF GRADING AND/OR OTHER PERMITS OR RIBBED WHEEL SHAKER OTHER SANCTIONS PROVIDED BY LAW." GRAVEL PAD 3" WASHED ROCK. 6" OWNER OR OWNER'S AGENT DATE WIND EROSION CONTROL TEMPORARY SEDIMENT CONTROL SE1 -SILT FENCE WE1 - WIND EROSION CONTROL EROSION CONTROL EC1 -SCHEDULING SE2 -SEDIMENT BASIN TEMPORARY TRACKING CONTROL TC1 -STABILIZED CONSTRUCTION ENTRANCE EXIT SE3 -SEDIMENT TRAP EC2 -PRESERVATION OF EXISTING VEGETATION TC2 -STABILIZED CONSTRUCTION ROADWAY SE4 -CHECK DAM EC3 -HYDRAULIC MULCH TC3 -ENTRANCE/OUTLET TIRE WASH SE5 -FIBER ROLLS EC4 -HYDROSEEDING SE6 -GRAVEL BAG BERM EC5 -SOIL BINDERS SE7 -STREET SWEEPING AND VACUUMING NON-STORMWATER MANAGEMENT EC6 -STRAW MULCH SE8 -SANDBAG BARRIER NS1 -WATER CONSERVATION PRACTICES EC7 -GEOTEXTILES & MATS STABILIZED CONSTRUCTION ENTRANCE: SE9 -STRAW BALE BARRIER NS2 - DEWATERING OPERATIONS EC8 - WOOD MULCHING SE10 -STORM DRAIN INLET PROTECTION NS3 -PAVING AND GRINDING OPERATIONS EC9 -EARTH DIKES AND DRAINAGE SWALES SE11 -ACTIVE TREATMENT SYSTEMS NS4 - TEMPORARY STREAM CROSSING **EROSION CONTROL PLAN** G7 EC10 - VELOCITY DISSIPATION DEVICES SE12 - TEMPORARY SILT DIKE NS5 - CLEAR WATER DIVERSION EC11 -SLOPE DRAINS SE13 - COMPOST SOCKS & BERMS NS6 -ILLICIT CONNECTION/DISCHARGE EC12 -STREAMBANK STABILIZATION SE14 -BIOFILTER BAGS CITY OF CERRITOS NS7 -POTABLE WATER/IRRIGATION DATE **REVISIONS** REVISED BY APPROVED BY EC13 -RESERVED WASTE MANAGEMENT & MATERIAL POLLUTION NS8 - VEHICLE AND EQUIPMENT CLEANING - EC14 -COMPOST BLANKETS VENTURA ENGINEERING INLAND, INC CONTROL NS9 - VEHICLE AND EQUIPMENT FUELING EC15 -SOIL PREPARATION\ROUGHENING 27393 YNEZ ROAD, SUITE 159 WM1 -MATERIAL DELIVERY AND STORAGE NS10 - VEHICLE AND EQUIPMENT MAINTENANCE EC16 -NON-VEGETATED STABILIZATION TEMECULA, CALIFORNIA 92591 WM2 -MATERIAL USE NS11 -PILE DRIVING OPERATIONS WILFREDO S.D. VENTURA PHONE: (951)252-7632 WM3 -STOCKPILE MANAGEMENT NS12 - CONCRETE CURING WILFREDO@VENTURAENGINEERINGINLAND.COM WM4 -SPILL PREVENTION AND CONTROL No. <u>66532</u> NS13 - CONCRETE FINISHING TYP. SECTION TYPICAL ELEVATION WM5 -SOLID WASTE MANAGEMENT NS14 -MATERIAL AND EQUIPMENT USE Exp. 6-30-24 Wilfredo Vinter WM6 -HAZARDOUS WASTE MANAGEMENT NS15 - DEMOLITION ADJACENT TO WATER CIVIL WM7 - CONTAMINATION SOIL MANAGEMENT STREET GRAVEL BAGS DETAIL: NS16 - TEMPORARY BATCH PLANTS Engineering Inland INC WILFREDO S.D. VENTURA DATE WM8 -CONCRETE WASTE MANAGEMENT RCE 66532, EXP. 6/30/24 WM9 -SANITARY/SEPTIC WASTE MANAGEMENT WM10 -LIQUID WASTE MANAGEMENT A.P.N. 7010-016-054 CIVIL SHEET 7 OF 7